

Illambazar Panchayet Samity Illambazar Birbhum

Schedule of work

Name of the work: - CONSTRUCTION OF NEW ICDS BUILDING AT NILDANGA
IN ILLAMBAZAR G.P. [From 2nd. SFC BZP Share 2008-2009 fund].

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-01

Item. No. (Page/ item)	Description of item.	Quantity	Rate. @ Rs.	Amount. Rs.
1. (1/2)	Earth work in excavation of foundation trenches or drain in all--- required complete.	9.563 cum	7329.27 / %cum	700.90
2. (5/4B)	Filling in foundation or plinth ---- by fine sand.	5.666 cum	34485.40 / %cum	1953.90
3. (3/3)	Earthwork in filling in foundation trenches or plinth etc. ----- quantity of work.	1.913 Cum.	4736.19 / %cum	90.60
4. (33/1)	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed ---	29.64 Sqm	194.65 /sqm	5769.40
5. (59/10/a)	Cement concrete with graded stone ballast (40mm size) ex/c shuttering. In ground floor. 6:3:1 proportion.	1.864 cum	3400.77 /cum	6339.00
6. (39/7)	Ordinary cement concrete (1:1.5:3) with graded stone chips (20mm size) ex/c shuttering --Pakur/Chandil variety. Ground floor	10.236 cum	4818.63 /cum	49,323.50
7. (69/22/a)	Brick with 1 st class bricks in cement mortar (6:1) In foundation & plinth:-	0.99 cum.	3283.12 /cum	3,250.30
8. (99/11)	25mm thick damp proof course-----. 19.20 x 0.25=4.80	4.80 Sqm.	146.42 /sqm	702.80
9. (69/22/b)	Brick with 1 st class bricks in cement mortar (6:1) In superstructure ground floor: -	8.903 cum.	3429.77 /cum	30,535.20
10. (63/12/f)	Hire and labour charges for shuttering with centering A. 25mm to 30mm th. Shuttering. Without staging.	23.13 Sqm	162.42 /sqm	3,756.80
(63/12/a)	B. 25mm to 30mm th. Wooden shuttering.	53.503 Sqm.	256.18 /sqm	13,706.40
11 (65/15)	Reinforcement for reinforced concrete work In all sorts of structure --Tor steel / Mild steel ---Ground floor: -	0.84 MT	55888.86 /M.T.	46,946.60
12. (319/2/ii/c)	Plaster (to wall, floor, ceiling) with sand and cement-Ground floor A. With (1:4) cement mortar (10mm th. Plaster.)	25.29 Sqm.	90.12 /sqm	2279.10
(319/2/i/b)	B. With (1:6) cement mortar (20mm th. Plaster.)	58.185 Sqm.	114.10 /sqm	6,638.90
(319/2/i/c)	C. With (1:6) cement mortar (15mm th. Plaster.)	66.78 Sqm	97.56 /sqm	6,515.10
13. (91/3)	Artificial stone in floor, dado, staircase with cement concrete (4:2:1) with stone chips ----- 25mm th. A.S.F--- ground floor:-	15.30 sqm	198.71 /sqm	3,040.30
14. (323/8)	Net cement punning about 1.5mm th. in wall, dado, window, sill, floor, drain etc.	15.975 sqm	28.33 /sqm	452.60
15. (155/10)	M.S. or W.I. ornamental grill of approved design joints continuously welded [Grill weight 16 Kg./ sqm. & above]	97.20 Kg.	6215.54 / Qntl	6,041.50
16. (351/5/ii)	Supply best Indian sheet glass ----- in/c fitted and fixed with nails and putty complete.	3.60 sqm	511.06 / sqm.	1839.80
17.	Wood work in door & window frame fitted & fixed	0.037	30623.00	1133.10

(179/1/i)	complete including a protective coat of painting---- (Other Local wood)	cum.	/cum	
18. [227/84/iii/b]	Panel shutters of door & window as per design (each panel consists of single plank without joints) ----- 25 mm. tk. Shutters with 12 mm. tk. Panels of size 30 to 45 cm. (Sisu, Gamar, Champ, Badam, Bhola, Morga, Hallak)	1.71 sqm	1809.94 /sqm.	3095.00
19.	Fittings of Door	01 Nos	L.S:- 500.00/N o	500.00
20. (343/7a)	a. Priming one coat on timber or plastered surface	5.325 Sqm.	28.18/sqm	150.10
(343/7b)	b. Priming one coat on Steel Surface or other metal surface	3.60 sqm	23.03/Sq m	82.90
21.	Painting with best quality synthetic enamel paint of approved make & brand including smoothening surface -- (With super gloss)			
(343/8a iv)	A. On timber or plastered surface	5.325 Sqm.	62.22 /sqm.	331.30
(345/8b iv)	B. On Steel Surface or other metal surface	3.60 sqm	53.73 /sqm.	193.40
22. (335/16)	Applying decorative cement base paint of approved quality---. In G.F. (Two coat)	57.465 sqm	39.48 /sqm	2268.70
23. (329/3)	White washing in/c cleaning & smoothening surface thoroughly ----- All floors, Three coats (on new works only).	76.425 sqm	1244.32 /%sqm.	951.00
Total:-Rs. 1, 98,608.20				
Note :- But the payment is resctricted upto Rs. 1,91,000.00				

[The nomenclature & rate collected from PW (W.B.) Sch.
As per mentioned page and item]

Signature of Tenderer: -



**Executive Officer
Illambazar Panchayet Samity**

Illambazar Panchayet Samity Illambazar Birbhum

Schedule of work

Name of the work: - - CONSTRUCTION OF NEW ICDS BUILDING AT METEKONA
IN BILATI G.P. [From 2nd. SFC BZP Share 2008-2009 fund].

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-02

Item. No. (Page/ item)	Description of item.	Quantity	Rate. @ Rs.	Amount. Rs.
1. (1/2)	Earth work in excavation of foundation trenches or drain in all--- required complete.	9.563 cum	7329.27 / %cum	700.90
2. (5/4B)	Filling in foundation or plinth ---- by fine sand.	5.666 cum	34485.40 / %cum	1953.90
3. (3/3)	Earthwork in filling in foundation trenches or plinth etc. ----- quantity of work.	1.913 Cum.	4736.19 / %cum	90.60
4. (33/1)	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed ---	29.64 Sqm	194.65 /sqm	5769.40
5. (59/10/a)	Cement concrete with graded stone ballast (40mm size) ex/c shuttering. In ground floor. 6:3:1 proportion.	1.864 cum	3400.77 /cum	6339.00
6. (39/7)	Ordinary cement concrete (1:1.5:3) with graded stone chips (20mm size) ex/c shuttering --Pakur/Chandil variety. Ground floor	10.236 cum	4818.63 /cum	49,323.50
7. (69/22/a)	Brick with 1 st class bricks in cement mortar (6:1) In foundation & plinth:-	0.99 cum.	3283.12 /cum	3,250.30
8. (99/11)	25mm thick damp proof course-----. 19.20 x 0.25=4.80	4.80 Sqm.	146.42 /sqm	702.80
9. (69/22/b)	Brick with 1 st class bricks in cement mortar (6:1) In superstructure ground floor: -	8.903 cum.	3429.77 /cum	30,535.20
10. (63/12/f)	Hire and labour charges for shuttering with centering A. 25mm to 30mm th. Shuttering. Without staging.	23.13 Sqm	162.42 /sqm	3,756.80
(63/12/a)	B. 25mm to 30mm th. Wooden shuttering.	53.503 Sqm.	256.18 /sqm	13,706.40
11 (65/15)	Reinforcement for reinforced concrete work In all sorts of structure --Tor steel / Mild steel ---Ground floor: -	0.84 MT	55888.86 /M.T.	46,946.60
12. (319/2/ii/c)	Plaster (to wall, floor, ceiling) with sand and cement-Ground floor A. With (1:4) cement mortar (10mm th. Plaster.)	25.29 Sqm.	90.12 /sqm	2279.10
(319/2/i/b)	B. With (1:6) cement mortar (20mm th. Plaster.)	58.185 Sqm.	114.10 /sqm	6,638.90
(319/2/i/c)	C. With (1:6) cement mortar (15mm th. Plaster.)	66.78 Sqm	97.56 /sqm	6,515.10
13. (91/3)	Artificial stone in floor, dado, staircase with cement concrete (4:2:1) with stone chips ----- 25mm th. A.S.F--- ground floor:-	15.30 sqm	198.71 /sqm	3,040.30
14. (323/8)	Net cement punning about 1.5mm th. in wall, dado, window, sill, floor, drain etc.	15.975 sqm	28.33 /sqm	452.60
15. (155/10)	M.S. or W.I. ornamental grill of approved design joints continuously welded [Grill weight 16 Kg./ sqm. & above]	97.20 Kg.	6215.54 / Qntl	6,041.50
16. (351/5/ii)	Supply best Indian sheet glass ----- in/c fitted and fixed with nails and putty complete.	3.60 sqm	511.06 / sqm.	1839.80
17.	Wood work in door & window frame fitted & fixed	0.037	30623.00	1133.10

(179/1/i)	complete including a protective coat of painting---- (Other Local wood)	cum.	/cum	
18. [227/84/iii/b]	Panel shutters of door & window as per design (each panel consists of single plank without joints) ----- 25 mm. tk. Shutters with 12 mm. tk. Panels of size 30 to 45 cm. (Sisu, Gamar, Champ, Badam, Bhola, Morga, Hallak)	1.71 sqm	1809.94 /sqm.	3095.00
19.	Fittings of Door	01 Nos	L.S:- 500.00/N o	500.00
20. (343/7a)	a. Priming one coat on timber or plastered surface	5.325 Sqm.	28.18/sqm	150.10
(343/7b)	b. Priming one coat on Steel Surface or other metal surface	3.60 sqm	23.03/Sq m	82.90
21. (343/8a iv)	Painting with best quality synthetic enamel paint of approved make & brand including smoothening surface -- (With super gloss)			
(345/8b iv)	B. On timber or plastered surface	5.325 Sqm.	62.22 /sqm.	331.30
	B. On Steel Surface or other metal surface	3.60 sqm	53.73 /sqm.	193.40
22. (335/16)	Applying decorative cement base paint of approved quality---. In G.F. (Two coat)	57.465 sqm	39.48 /sqm	2268.70
23. (329/3)	White washing in/c cleaning & smoothening surface thoroughly ----- All floors, Three coats (on new works only).	76.425 sqm	1244.32 / %sqm.	951.00
Total:-Rs. 1, 98,608.20				
Note :- But the payment is resctricted upto Rs. 1,91,000.00				

[The nomenclature & rate collected from PW (W.B.) Sch.
As per mentioned page and item]

Signature of Tenderer: -



Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity Illambazar Birbhum

Schedule of work

Name of the work: - CONSTRUCTION OF NEW ICDS BUILDING AT DARANDA ADIBASIPARA
IN ILLAMBAZAR G.P. [From 2nd. SFC BZP Share 2008-2009 fund].

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-03

Item. No. (Page/ item)	Description of item.	Quantity	Rate. @ Rs.	Amount. Rs.
1. (1/2)	Earth work in excavation of foundation trenches or drain in all--- required complete.	9.563 cum	7329.27 / %cum	700.90
2. (5/4B)	Filling in foundation or plinth ---- by fine sand.	5.666 cum	34485.40 / %cum	1953.90
3. (3/3)	Earthwork in filling in foundation trenches or plinth etc. ----- quantity of work.	1.913 Cum.	4736.19 / %cum	90.60
4. (33/1)	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed ---	29.64 Sqm	194.65 /sqm	5769.40
5. (59/10/a)	Cement concrete with graded stone ballast (40mm size) ex/c shuttering. In ground floor. 6:3:1 proportion.	1.864 cum	3400.77 /cum	6339.00
6. (39/7)	Ordinary cement concrete (1:1.5:3) with graded stone chips (20mm size) ex/c shuttering --Pakur/Chandil variety. Ground floor	10.236 cum	4818.63 /cum	49,323.50
7. (69/22/a)	Brick with 1 st class bricks in cement mortar (6:1) In foundation & plinth:-	0.99 cum.	3283.12 /cum	3,250.30
8. (99/11)	25mm thick damp proof course-----. 19.20 x 0.25=4.80	4.80 Sqm.	146.42 /sqm	702.80
9. (69/22/b)	Brick with 1 st class bricks in cement mortar (6:1) In superstructure ground floor: -	8.903 cum.	3429.77 /cum	30,535.20
10. (63/12/f)	Hire and labour charges for shuttering with centering A. 25mm to 30mm th. Shuttering. Without staging.	23.13 Sqm	162.42 /sqm	3,756.80
(63/12/a)	B. 25mm to 30mm th. Wooden shuttering.	53.503 Sqm.	256.18 /sqm	13,706.40
11 (65/15)	Reinforcement for reinforced concrete work In all sorts of structure --Tor steel / Mild steel ---Ground floor: -	0.84 MT	55888.86 /M.T.	46,946.60
12. (319/2/ii/c)	Plaster (to wall, floor, ceiling) with sand and cement-Ground floor A. With (1:4) cement mortar (10mm th. Plaster.)	25.29 Sqm.	90.12 /sqm	2279.10
(319/2/i/b)	B. With (1:6) cement mortar (20mm th. Plaster.)	58.185 Sqm.	114.10 /sqm	6,638.90
(319/2/i/c)	C. With (1:6) cement mortar (15mm th. Plaster.)	66.78 Sqm	97.56 /sqm	6,515.10
13. (91/3)	Artificial stone in floor, dado, staircase with cement concrete (4:2:1) with stone chips ----- 25mm th. A.S.F--- ground floor:-	15.30 sqm	198.71 /sqm	3,040.30
14. (323/8)	Net cement punning about 1.5mm th. in wall, dado, window, sill, floor, drain etc.	15.975 sqm	28.33 /sqm	452.60
15. (155/10)	M.S. or W.I. ornamental grill of approved design joints continuously welded [Grill weight 16 Kg./ sqm. & above]	97.20 Kg.	6215.54 / Qntl	6,041.50
16. (351/5/ii)	Supply best Indian sheet glass ----- in/c fitted and fixed with nails and putty complete.	3.60 sqm	511.06 / sqm.	1839.80
17.	Wood work in door & window frame fitted & fixed	0.037	30623.00	1133.10

(179/1/i)	complete including a protective coat of painting---- (Other Local wood)	cum.	/cum	
18. [227/84/iii/b]	Panel shutters of door & window as per design (each panel consists of single plank without joints) ----- 25 mm. tk. Shutters with 12 mm. tk. Panels of size 30 to 45 cm. (Sisu, Gamar, Champ, Badam, Bhola, Morga, Hallak)	1.71 sqm	1809.94 /sqm.	3095.00
19.	Fittings of Door	01 Nos	L.S:- 500.00/N o	500.00
20. (343/7a)	a. Priming one coat on timber or plastered surface	5.325 Sqm.	28.18/sqm	150.10
(343/7b)	b. Priming one coat on Steel Surface or other metal surface	3.60 sqm	23.03/Sq m	82.90
21.	Painting with best quality synthetic enamel paint of approved make & brand including smoothening surface -- (With super gloss)			
(343/8a iv)	C. On timber or plastered surface	5.325 Sqm.	62.22 /sqm.	331.30
(345/8b iv)	B. On Steel Surface or other metal surface	3.60 sqm	53.73 /sqm.	193.40
22. (335/16)	Applying decorative cement base paint of approved quality---. In G.F. (Two coat)	57.465 sqm	39.48 /sqm	2268.70
23. (329/3)	White washing in/c cleaning & smoothening surface thoroughly ----- All floors, Three coats (on new works only).	76.425 sqm	1244.32 /%sqm.	951.00
Total:-Rs. 1, 98,608.20				
Note :- But the payment is resctricted upto Rs. 1,91,000.00				

[The nomenclature & rate collected from PW (W.B.) Sch.
As per mentioned page and item]

Signature of Tenderer: -



**Executive Officer
Illambazar Panchayet Samity**

Illambazar Panchayet Samity Illambazar Birbhum

Schedule of work

Name of the work: - CONSTRUCTION OF NEW ICDS BUILDING AT BATIKAR ADIBASIPARA
IN BATIKAR G.P. [From 2nd. SFC BZP Share 2008-2009 fund].

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-04

Item. No. (Page/ item)	Description of item.	Quantity	Rate. @ Rs.	Amount. Rs.
1. (1/2)	Earth work in excavation of foundation trenches or drain in all--- required complete.	9.563 cum	7329.27 / %cum	700.90
2. (5/4B)	Filling in foundation or plinth ---- by fine sand.	5.666 cum	34485.40 / %cum	1953.90
3. (3/3)	Earthwork in filling in foundation trenches or plinth etc. ----- quantity of work.	1.913 Cum.	4736.19 / %cum	90.60
4. (33/1)	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed ---	29.64 Sqm	194.65 /sqm	5769.40
5. (59/10/a)	Cement concrete with graded stone ballast (40mm size) ex/c shuttering. In ground floor. 6:3:1 proportion.	1.864 cum	3400.77 /cum	6339.00
6. (39/7)	Ordinary cement concrete (1:1.5:3) with graded stone chips (20mm size) ex/c shuttering --Pakur/Chandil variety. Ground floor	10.236 cum	4818.63 /cum	49,323.50
7. (69/22/a)	Brick with 1 st class bricks in cement mortar (6:1) In foundation & plinth:-	0.99 cum.	3283.12 /cum	3,250.30
8. (99/11)	25mm thick damp proof course-----. 19.20 x 0.25=4.80	4.80 Sqm.	146.42 /sqm	702.80
9. (69/22/b)	Brick with 1 st class bricks in cement mortar (6:1) In superstructure ground floor: -	8.903 cum.	3429.77 /cum	30,535.20
10. (63/12/f)	Hire and labour charges for shuttering with centering A. 25mm to 30mm th. Shuttering. Without staging.	23.13 Sqm	162.42 /sqm	3,756.80
(63/12/a)	B. 25mm to 30mm th. Wooden shuttering.	53.503 Sqm.	256.18 /sqm	13,706.40
11 (65/15)	Reinforcement for reinforced concrete work In all sorts of structure --Tor steel / Mild steel ---Ground floor: -	0.84 MT	55888.86 /M.T.	46,946.60
12. (319/2/ii/c)	Plaster (to wall, floor, ceiling) with sand and cement-Ground floor A. With (1:4) cement mortar (10mm th. Plaster.)	25.29 Sqm.	90.12 /sqm	2279.10
(319/2/i/b)	B. With (1:6) cement mortar (20mm th. Plaster.)	58.185 Sqm.	114.10 /sqm	6,638.90
(319/2/i/c)	C. With (1:6) cement mortar (15mm th. Plaster.)	66.78 Sqm	97.56 /sqm	6,515.10
13. (91/3)	Artificial stone in floor, dado, staircase with cement concrete (4:2:1) with stone chips ----- 25mm th. A.S.F--- ground floor:-	15.30 sqm	198.71 /sqm	3,040.30
14. (323/8)	Net cement punning about 1.5mm th. in wall, dado, window, sill, floor, drain etc.	15.975 sqm	28.33 /sqm	452.60
15. (155/10)	M.S. or W.I. ornamental grill of approved design joints continuously welded [Grill weight 16 Kg./ sqm. & above]	97.20 Kg.	6215.54 / Qntl	6,041.50
16. (351/5/ii)	Supply best Indian sheet glass ----- in/c fitted and fixed with nails and putty complete.	3.60 sqm	511.06 / sqm.	1839.80
17.	Wood work in door & window frame fitted & fixed	0.037	30623.00	1133.10

(179/1/i)	complete including a protective coat of painting---- (Other Local wood)	cum.	/cum	
18. [227/84/iii/b]	Panel shutters of door & window as per design (each panel consists of single plank without joints) ----- 25 mm. tk. Shutters with 12 mm. tk. Panels of size 30 to 45 cm. (Sisu, Gamar, Champ, Badam, Bhola, Morga, Hallak)	1.71 sqm	1809.94 /sqm.	3095.00
19.	Fittings of Door	01 Nos	L.S:- 500.00/N o	500.00
20. (343/7a)	a. Priming one coat on timber or plastered surface	5.325 Sqm.	28.18/sqm	150.10
(343/7b)	b. Priming one coat on Steel Surface or other metal surface	3.60 sqm	23.03/Sq m	82.90
21. (343/8a iv)	Painting with best quality synthetic enamel paint of approved make & brand including smoothening surface -- (With super gloss)			
(345/8b iv)	D. On timber or plastered surface	5.325 Sqm.	62.22 /sqm.	331.30
	B. On Steel Surface or other metal surface	3.60 sqm	53.73 /sqm.	193.40
22. (335/16)	Applying decorative cement base paint of approved quality---. In G.F. (Two coat)	57.465 sqm	39.48 /sqm	2268.70
23. (329/3)	White washing in/c cleaning & smoothening surface thoroughly ----- All floors, Three coats (on new works only).	76.425 sqm	1244.32 /%sqm.	951.00
Total:-Rs. 1, 98,608.20				
Note :- But the payment is resctricted upto Rs. 1,91,000.00				

[The nomenclature & rate collected from PW (W.B.) Sch.
As per mentioned page and item]

Signature of Tenderer: -



Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity Illambazar Birbhum

Schedule of work

Name of the work: - CONSTRUCTION OF NEW ICDS BUILDING AT KAYRA ADIBASIPARA
IN NANASOLE G.P. [From 2nd. SFC BZP Share 2008-2009 fund].

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-05

Item. No. (Page/ item)	Description of item.	Quantity	Rate. @ Rs.	Amount. Rs.
1. (1/2)	Earth work in excavation of foundation trenches or drain in all--- required complete.	9.563 cum	7329.27 / %cum	700.90
2. (5/4B)	Filling in foundation or plinth ---- by fine sand.	5.666 cum	34485.40 / %cum	1953.90
3. (3/3)	Earthwork in filling in foundation trenches or plinth etc. ----- quantity of work.	1.913 Cum.	4736.19 / %cum	90.60
4. (33/1)	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed ---	29.64 Sqm	194.65 /sqm	5769.40
5. (59/10/a)	Cement concrete with graded stone ballast (40mm size) ex/c shuttering. In ground floor. 6:3:1 proportion.	1.864 cum	3400.77 /cum	6339.00
6. (39/7)	Ordinary cement concrete (1:1.5:3) with graded stone chips (20mm size) ex/c shuttering --Pakur/Chandil variety. Ground floor	10.236 cum	4818.63 /cum	49,323.50
7. (69/22/a)	Brick with 1 st class bricks in cement mortar (6:1) In foundation & plinth:-	0.99 cum.	3283.12 /cum	3,250.30
8. (99/11)	25mm thick damp proof course-----. 19.20 x 0.25=4.80	4.80 Sqm.	146.42 /sqm	702.80
9. (69/22/b)	Brick with 1 st class bricks in cement mortar (6:1) In superstructure ground floor: -	8.903 cum.	3429.77 /cum	30,535.20
10. (63/12/f)	Hire and labour charges for shuttering with centering A. 25mm to 30mm th. Shuttering. Without staging.	23.13 Sqm	162.42 /sqm	3,756.80
(63/12/a)	B. 25mm to 30mm th. Wooden shuttering.	53.503 Sqm.	256.18 /sqm	13,706.40
11 (65/15)	Reinforcement for reinforced concrete work In all sorts of structure --Tor steel / Mild steel ---Ground floor: -	0.84 MT	55888.86 /M.T.	46,946.60
12. (319/2/ii/c)	Plaster (to wall, floor, ceiling) with sand and cement-Ground floor A. With (1:4) cement mortar (10mm th. Plaster.)	25.29 Sqm.	90.12 /sqm	2279.10
(319/2/i/b)	B. With (1:6) cement mortar (20mm th. Plaster.)	58.185 Sqm.	114.10 /sqm	6,638.90
(319/2/i/c)	C. With (1:6) cement mortar (15mm th. Plaster.)	66.78 Sqm	97.56 /sqm	6,515.10
13. (91/3)	Artificial stone in floor, dado, staircase with cement concrete (4:2:1) with stone chips ----- 25mm th. A.S.F--- ground floor:-	15.30 sqm	198.71 /sqm	3,040.30
14. (323/8)	Net cement punning about 1.5mm th. in wall, dado, window, sill, floor, drain etc.	15.975 sqm	28.33 /sqm	452.60
15. (155/10)	M.S. or W.I. ornamental grill of approved design joints continuously welded [Grill weight 16 Kg./ sqm. & above]	97.20 Kg.	6215.54 / Qntl	6,041.50
16. (351/5/ii)	Supply best Indian sheet glass ----- in/c fitted and fixed with nails and putty complete.	3.60 sqm	511.06 / sqm.	1839.80
17.	Wood work in door & window frame fitted & fixed	0.037	30623.00	1133.10

(179/1/i)	complete including a protective coat of painting---- (Other Local wood)	cum.	/cum	
18. [227/84/iii/b]	Panel shutters of door & window as per design (each panel consists of single plank without joints) ----- 25 mm. tk. Shutters with 12 mm. tk. Panels of size 30 to 45 cm. (Sisu, Gamar, Champ, Badam, Bhola, Morga, Hallak)	1.71 sqm	1809.94 /sqm.	3095.00
19.	Fittings of Door	01 Nos	L.S:- 500.00/N o	500.00
20. (343/7a)	a. Priming one coat on timber or plastered surface	5.325 Sqm.	28.18/sqm	150.10
(343/7b)	b. Priming one coat on Steel Surface or other metal surface	3.60 sqm	23.03/Sq m	82.90
21.	Painting with best quality synthetic enamel paint of approved make & brand including smoothening surface -- (With super gloss)			
(343/8a iv)	E. On timber or plastered surface	5.325 Sqm.	62.22 /sqm.	331.30
(345/8b iv)	B. On Steel Surface or other metal surface	3.60 sqm	53.73 /sqm.	193.40
22. (335/16)	Applying decorative cement base paint of approved quality---. In G.F. (Two coat)	57.465 sqm	39.48 /sqm	2268.70
23. (329/3)	White washing in/c cleaning & smoothening surface thoroughly ----- All floors, Three coats (on new works only).	76.425 sqm	1244.32 /%sqm.	951.00
Total:-Rs. 1, 98,608.20				
Note :- But the payment is resctricted upto Rs. 1,91,000.00				

[The nomenclature & rate collected from PW (W.B.) Sch.
As per mentioned page and item]

Signature of Tenderer: -



**Executive Officer
Illambazar Panchayet Samity**

Illambazar Panchayet Samity
Illambazar Birbhum

SCHEDULE OF WORK FOR CONSTRUCTION OF ICDS BUILDING AT UDAYPUR UNDER
GHURISHA G.P. WITHIN ILLAMBAZAR PANCHAYET SAMITY UNDER B.R.G.F.(ZP
SHARE)2008-2009

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-06

Sl.No.	Description of item	Total Qty	Unit	Rate in/c 1% cess	Amount
1	Earth work in excaation in foundation trenches or drains in all osrts of Soil (in/c mixed soil but excluding laterite or sand stone) including removing , spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches levelling dressing and ramming the bottom, balling out water as required complite. Depth of excavation not exceeding 1.5 mtrs.(Page No-1,it-2)	37.29	m3	73.29	2732.98
2	Singal layer brick flat soling of picked jhama bricks in/c ramming and dressing bed to proper level and filling joints with powered earth or local sand.(page-33,it-1)	54.78	m2	194.65	10663.15
3	Cement concrete with graded stone ballast(40mm size excluding shuttering inground floor(1:3:6).)(page-59,it-10b)	2.0	m3	3400.77	6801.54
4	Ordinary cement concrete(mix 3:1.5:1)with graded stone chips (20mm down) excluding shuttering and reinforcement, if any, in ground floor as per IS 456-2000.(page-39,it-7)	12.60	m3	4818.63	60714.74
5	Filling in foundation or plinth by silver sand in layers not exceeding 150mm as directed and consolidating same by through saturation with water ramming complete in/c the cost of supplyof sand by fine snad (page-5,it-4B)	20.58	m3	344.85	7097.01
6	Earth work in filling in foundation trenches or plinth with good earth in layers not exceeding 150mm in/c watering and ramming etc layer by layer complete.	16.54	m3	47.36	783.33
7	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in foundation and plinth	7.3	m3	3283.12	23966.78
8	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in superstructure of Ground floor	12.48	m3	3429.77	42803.53
9	125mm. Thick brick work with 1st class bricks in cement mortar(4:1) in ground floor.	17.83	m2	460.52	8211.07
10	Hire and labour charges for shuttering with centering and necessary staging upto 4mt. Using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slab,beams, columns, lintels curved or straight in/c fitting fixing and striking out after completion of works.(page-63,it-12a,f)	74.92	m2	256.18	19193.01
11	25mm thick damp proof course with cement concrete with stone chips(4:2:1) with graded stone aggregate 10mm size and admixture of water proofing compound as per manufacturer's specification.(page-99, it-11)	4.76	m2	146.42	696.96

12	Reinforcement for reinforced concrete work in all sorts of structures in/c distribution bars, stirrups, binders etc.in/c supply of rods,initial straightening and removal of loose rust,cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16gauge black annealed wire at every intersection, complete as per drawing and direction.Tor steel.(page-65,it-15a)	1.088	M.T.	55888.9	60807.08
	Plaster(in wall, floor.etc) with sand and cement mortar in/c rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface in/c throating, nosing and drip course where necessary. (page-319,it-2)				
	13(i) with 4:1 cement mortar,10mmth, ceiling.	45.31	m2	90.12	4083.34
	14(ii) with(6:1) cement plaster,20mmth.Inside.	53.66	m2	114.1	6122.61
	15(iii) with(6:1) cement plaster,15mmth. outside.	116.7	m2	97.56	11385.25
16	Neat cement punning about 1.5mm thick in wall, dado>window, floor, drain etc.(page-323,it-8)	27.8	m2	28.33	787.29
				Total	266849.66
				Total	266849.66
17	Artificial stone floor, dado,staircase etc. with cement concrete(4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion2:1 in/c smooth finishing and rounding off corners and in/c application of cement slurry before flooring works using cement@1.75kg/sq-m. all complete in/c all materials and labour. In ground floor25mm th.(page-91,it-3ii)	27.77	m2	198.71	5518.18
18	White washing including cleaning and emoothing surface throughly three coats on new work only.	119.42	m2	12.44	1485.58
19	Applying decorative cement based paint of approved quality after preparing the surface in/c scraping the same thoroughly as per manufacturer's specification.(page-335,it-16iii)	80.11	m2	39.48	3162.74
20	Protective and decorative textured exterior high class matt finish, composed of special tharmoplastic resin containing fine crystalline-----in ground floor two coats.	5.12	m2	91.81	470.07
21	Wood work in door and window frame fitted and fixed complete in/c a protective coat of painting at the contact surface of the frame with jam wood.(page-179,it-1h)	0.188	m3	30623.0	5766.31
22	M.S or W.I. ornamental grill of approved design joints continuously welded with M.S. or W.I. flats and bars for windows, railings,etc fitted and fixed with necessary screws and lugs in ground floor.Grill weighing above 10kg/sq-m and upto16kg/aq-m.(page-155,it-10i)	39.82	kg	56.27	2240.67
23	Z-batten shutters of door and window as per design havings tongued and groov half lap jointed as per direction of the EIC including fitting and fixing shutter in position but excluding the cost of hinges and other fittings.25mm thick planks,19mm thick battens.	4.61	m2	1359.86	6268.95
24	M.S.calmp for gixing door and window frame made of flat bent bar,end bifurcated, fixed in cement concrete with stone chips(4:2:1) fitted and fixed complete as per direction.40mmx6mm ,200mm length.(page-189,it-18b)	24	No	22.8	547.20
	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.(page-191,it-20iii)				
	100mmx50mmx1.25mm	8	No	41.12	328.96
25	75mmx40mmx1.12mm	24	No	25.61	614.64

	Iron socket bolt of approved quality fitted and fixed complete.(page-197,it-25b,c)				
26	Door-225mm longx 10mm dia bolt	2	No	79.4	158.8
	Window-100mm longx 10mm dia bolt	12	No	32.15	385.8
27	Iron hasp bolt of approved quality fitted and fixed complete with 16mm dia rod with centre bolt and round fitting.(page-199,it-27b)				
	Door-250mmx 16mm dia bolt	2	No	182.66	365.32
28	Iron door handle of approved quality manufactured from extruded section conforming to I.S. specification fitted and fixed complete.				
	100mmx5mm	12	No	36.64	439.68
	150mmx5.5mm	4	No	46.01	184.04
29	Priming one coat on timber, plastered or on steel surface with sythetic enamel/oil bound primer of approved quality in/c smoothening surface by sand papering etc.(page-343,it-7a)	17.78	m2	28.18	501.04
30	Painting with best quality sythetic rnameal paint of approved make and brand in/c smoothening surface by sand papering etc. in/c using of approved putty etc. on the surface.(page-343,it-8aiv)other than high gloss	17.78	m2	53.73	955.32
31	G.I. rain water spout 75mm dia and 600 to 750mm long supplied fitted and fixed complete with two coats of paint to both exposed portion	4	No	136.35	545.4
				Total	296788.37

Signature of Tenderer: -



Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity
Illambazar Birbhum

SCHEDULE OF WORK FOR CONSTRUCTION OF ICDS BUILDING AT KHUDRAPUR UNDER
GHURISHA G.P. WITHIN ILLAMBAZAR PANCHAYET SAMITY UNDER B.R.G.F.(ZP
SHARE)2008-2009

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-07

Sl.No.	Description of item	Total Qty	Unit	Rate in/c 1% cess	Amount
1	Earth work in excaation in foundation trenches or drains in all osrts of Soil (in/c mixed soil but excluding laterite or sand stone) including removing , spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches levelling dressing and ramming the bottom, balling out water as required complite. Depth of excavation not exceeding 1.5 mtrs.(Page No-1,it-2)	37.29	m3	73.29	2732.98
2	Singal layer brick flat soling of picked jhama bricks in/c ramming and dressing bed to proper level and filling joints with powered earth or local sand.(page-33,it-1)	54.78	m2	194.65	10663.15
3	Cement concrete with graded stone ballast(40mm size excluding shuttering inground floor(1:3:6).)(page-59,it-10b)	2.0	m3	3400.77	6801.54
4	Ordinary cement concrete(mix 3:1.5:1)with graded stone chips (20mm down) excluding shuttering and reinforcement, if any, in ground floor as per IS 456-2000.(page-39,it-7)	12.60	m3	4818.63	60714.74
5	Filling in foundation or plinth by silver sand in layers not exceeding 150mm as directed and consolidating same by through saturation with water ramming complete in/c the cost of supplyof sand by fine snad (page-5,it-4B)	20.58	m3	344.85	7097.01
6	Earth work in filling in foundation trenches or plinth with good earth in layers not exceeding 150mm in/c watering and ramming etc layer by layer complete.	16.54	m3	47.36	783.33
7	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in foundation and plinth	7.3	m3	3283.12	23966.78
8	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in superstructure of Ground floor	12.48	m3	3429.77	42803.53
9	125mm. Thick brick work with 1st class bricks in cement mortar(4:1) in ground floor.	17.83	m2	460.52	8211.07
10	Hire and labour charges for shuttering with centering and necessary staging upto 4mt. Using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slab,beams, columns, lintels curved or straight in/c fitting fixing and striking out after completion of works.(page-63,it-12a,f)	74.92	m2	256.18	19193.01
11	25mm thick damp proof course with cement concrete with stone chips(4:2:1) with graded stone aggregate 10mm size and admixture of water proofing compound as per manufacturer's specification.(page-99, it-11)	4.76	m2	146.42	696.96

12	Reinforcement for reinforced concrete work in all sorts of structures in/c distribution bars, stirrups, binders etc.in/c supply of rods,initial straightening and removal of loose rust,cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16gauge black annealed wire at every intersection, complete as per drawing and direction.Tor steel.(page-65,it-15a)	1.088	M.T.	55888.9	60807.08
	Plaster(in wall, floor.etc) with sand and cement mortar in/c rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface in/c throating, nosing and drip course where necessary. (page-319,it-2)				
	13(i) with 4:1 cement mortar,10mmth, ceiling.	45.31	m2	90.12	4083.34
	14(ii) with(6:1) cement plaster,20mmth.Inside.	53.66	m2	114.1	6122.61
	15(iii) with(6:1) cement plaster,15mmth. outside.	116.7	m2	97.56	11385.25
16	Neat cement punning about 1.5mm thick in wall, dado>window, floor, drain etc.(page-323,it-8)	27.8	m2	28.33	787.29
				Total	266849.66
				Total	266849.66
17	Artificial stone floor, dado,staircase etc. with cement concrete(4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion2:1 in/c smooth finishing and rounding off corners and in/c application of cement slurry before flooring works using cement@1.75kg/sq-m. all complete in/c all materials and labour. In ground floor25mm th.(page-91,it-3ii)	27.77	m2	198.71	5518.18
18	White washing including cleaning and emoothing surface throughly three coats on new work only.	119.42	m2	12.44	1485.58
19	Applying decorative cement based paint of approved quality after preparing the surface in/c scraping the same thoroughly as per manufacturer's specification.(page-335,it-16iii)	80.11	m2	39.48	3162.74
20	Protective and decorative textured exterior high class matt finish, composed of special tharmoplastic resin containing fine crystalline-----in ground floor two coats.	5.12	m2	91.81	470.07
21	Wood work in door and window frame fitted and fixed complete in/c a protective coat of painting at the contact surface of the frame with jam wood.(page-179,it-1h)	0.188	m3	30623.0	5766.31
22	M.S or W.I. ornamental grill of approved design joints continuously welded with M.S. or W.I. flats and bars for windows, railings,etc fitted and fixed with necessary screws and lugs in ground floor.Grill weighing above 10kg/sq-m and upto16kg/aq-m.(page-155,it-10i)	39.82	kg	56.27	2240.67
23	Z-batten shutters of door and window as per design havings tongued and groov half lap jointed as per direction of the EIC including fitting and fixing shutter in position but excluding the cost of hinges and other fittings.25mm thick planks,19mm thick battens.	4.61	m2	1359.86	6268.95
24	M.S.calmp for gixing door and window frame made of flat bent bar,end bifurcated, fixed in cement concrete with stone chips(4:2:1) fitted and fixed complete as per direction.40mmx6mm ,200mm length.(page-189,it-18b)	24	No	22.8	547.20
	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.(page-191,it-20iii)				
	100mmx50mmx1.25mm	8	No	41.12	328.96
25	75mmx40mmx1.12mm	24	No	25.61	614.64

	Iron socket bolt of approved quality fitted and fixed complete.(page-197,it-25b,c)				
26	Door-225mm longx 10mm dia bolt	2	No	79.4	158.8
	Window-100mm longx 10mm dia bolt	12	No	32.15	385.8
27	Iron hasp bolt of approved quality fitted and fixed complete with 16mm dia rod with centre bolt and round fitting.(page-199,it-27b)				
	Door-250mmx 16mm dia bolt	2	No	182.66	365.32
28	Iron door handle of approved quality manufactured from extruded section conforming to I.S. specification fitted and fixed complete.				
	100mmx5mm	12	No	36.64	439.68
	150mmx5.5mm	4	No	46.01	184.04
29	Priming one coat on timber, plastered or on steel surface with sythetic enamel/oil bound primer of approved quality in/c smoothening surface by sand papering etc.(page-343,it-7a)	17.78	m2	28.18	501.04
30	Painting with best quality sythetic rnameal paint of approved make and brand in/c smoothening surface by sand papering etc. in/c using of approved putty etc. on the surface.(page-343,it-8aiv)other than high gloss	17.78	m2	53.73	955.32
31	G.I. rain water spout 75mm dia and 600 to 750mm long supplied fitted and fixed complete with two coats of paint to both exposed portion	4	No	136.35	545.4
				Total	296788.37

Signature of Tenderer: -



Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity
Illambazar Birbhum

SCHEDULE OF WORK FOR CONSTRUCTION OF ICDS BUILDING AT NETAJI COLONY
UNDER GHURISHA G.P. WITHIN ILLAMBAZAR PANCHAYET SAMITY UNDER B.R.G.F.(ZP
SHARE)2008-2009

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011


Sl. No.-08

Sl.No.	Description of item	Total Qty	Unit	Rate in/c 1% cess	Amount
1	Earth work in excaation in foundation trenches or drains in all osrts of Soil (in/c mixed soil but excluding laterite or sand stone) including removing , spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches levelling dressing and ramming the bottom, balling out water as required complite. Depth of excavation not exceeding 1.5 mtrs.(Page No-1,it-2)	37.29	m3	73.29	2732.98
2	Singal layer brick flat soling of picked jhama bricks in/c ramming and dressing bed to proper level and filling joints with powered earth or local sand.(page-33,it-1)	54.78	m2	194.65	10663.15
3	Cement concrete with graded stone ballast(40mm size excluding shuttering inground floor(1:3:6).)(page-59,it-10b)	2.0	m3	3400.77	6801.54
4	Ordinary cement concrete(mix 3:1.5:1)with graded stone chips (20mm down) excluding shuttering and reinforcement, if any, in ground floor as per IS 456-2000.(page-39,it-7)	12.60	m3	4818.63	60714.74
5	Filling in foundation or plinth by silver sand in layers not exceeding 150mm as directed and consolidating same by through saturation with water ramming complete in/c the cost of supplyof sand by fine snad (page-5,it-4B)	20.58	m3	344.85	7097.01
6	Earth work in filling in foundation trenches or plinth with good earth in layers not exceeding 150mm in/c watering and ramming etc layer by layer complete.	16.54	m3	47.36	783.33
7	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in foundation and plinth	7.3	m3	3283.12	23966.78
8	Brick work with 1st class bricks in cement mortar(6:1).(page-69,it-22)in superstructure of Ground floor	12.48	m3	3429.77	42803.53
9	125mm. Thick brick work with 1st class bricks in cement mortar(4:1) in ground floor.	17.83	m2	460.52	8211.07
10	Hire and labour charges for shuttering with centering and necessary staging upto 4mt. Using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slab,beams, columns, lintels curved or straight in/c fitting fixing and striking out after completion of works.(page-63,it-12a,f)	74.92	m2	256.18	19193.01
11	25mm thick damp proof course with cement concrete with stone chips(4:2:1) with graded stone aggregate 10mm size and admixture of water proofing compound as per manufacturer's specification.(page-99, it-11)	4.76	m2	146.42	696.96

12	Reinforcement for reinforced concrete work in all sorts of structures in/c distribution bars, stirrups, binders etc.in/c supply of rods,initial straightening and removal of loose rust,cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16gauge black annealed wire at every intersection, complete as per drawing and direction.Tor steel.(page-65,it-15a)	1.088	M.T.	55888.9	60807.08
	Plaster(in wall, floor.etc) with sand and cement mortar in/c rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface in/c throating, nosing and drip course where necessary. (page-319,it-2)				
	13(i) with 4:1 cement mortar,10mmth, ceiling.	45.31	m2	90.12	4083.34
	14(ii) with(6:1) cement plaster,20mmth.Inside.	53.66	m2	114.1	6122.61
	15(iii) with(6:1) cement plaster,15mmth. outside.	116.7	m2	97.56	11385.25
16	Neat cement punning about 1.5mm thick in wall, dado>window, floor, drain etc.(page-323,it-8)	27.8	m2	28.33	787.29
				Total	266849.66
				Total	266849.66
17	Artificial stone floor, dado,staircase etc. with cement concrete(4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion2:1 in/c smooth finishing and rounding off corners and in/c application of cement slurry before flooring works using cement@1.75kg/sq-m. all complete in/c all materials and labour. In ground floor25mm th.(page-91,it-3ii)	27.77	m2	198.71	5518.18
18	White washing including cleaning and emoothing surface throughly three coats on new work only.	119.42	m2	12.44	1485.58
19	Applying decorative cement based paint of approved quality after preparing the surface in/c scraping the same thoroughly as per manufacturer's specification.(page-335,it-16iii)	80.11	m2	39.48	3162.74
20	Protective and decorative textured exterior high class matt finish, composed of special tharmoplastic resin containing fine crystalline-----in ground floor two coats.	5.12	m2	91.81	470.07
21	Wood work in door and window frame fitted and fixed complete in/c a protective coat of painting at the contact surface of the frame with jam wood.(page-179,it-1h)	0.188	m3	30623.0	5766.31
22	M.S or W.I. ornamental grill of approved design joints continuously welded with M.S. or W.I. flats and bars for windows, railings,etc fitted and fixed with necessary screws and lugs in ground floor.Grill weighing above 10kg/sq-m and upto16kg/aq-m.(page-155,it-10i)	39.82	kg	56.27	2240.67
23	Z-batten shutters of door and window as per design havings tongued and groov half lap jointed as per direction of the EIC including fitting and fixing shutter in position but excluding the cost of hinges and other fittings.25mm thick planks,19mm thick battens.	4.61	m2	1359.86	6268.95
24	M.S.calmp for gixing door and window frame made of flat bent bar,end bifurcated, fixed in cement concrete with stone chips(4:2:1) fitted and fixed complete as per direction.40mmx6mm ,200mm length.(page-189,it-18b)	24	No	22.8	547.20
	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.(page-191,it-20iii)				
	100mmx50mmx1.25mm	8	No	41.12	328.96
25	75mmx40mmx1.12mm	24	No	25.61	614.64

	Iron socket bolt of approved quality fitted and fixed complete.(page-197,it-25b,c)				
26	Door-225mm longx 10mm dia bolt	2	No	79.4	158.8
	Window-100mm longx 10mm dia bolt	12	No	32.15	385.8
27	Iron hasp bolt of approved quality fitted and fixed complete with 16mm dia rod with centre bolt and round fitting.(page-199,it-27b)				
	Door-250mmx 16mm dia bolt	2	No	182.66	365.32
28	Iron door handle of approved quality manufactured from extruded section conforming to I.S. specification fitted and fixed complete.				
	100mmx5mm	12	No	36.64	439.68
	150mmx5.5mm	4	No	46.01	184.04
29	Priming one coat on timber, plastered or on steel surface with sythetic enamel/oil bound primer of approved quality in/c smoothening surface by sand papering etc.(page-343,it-7a)	17.78	m2	28.18	501.04
30	Painting with best quality sythetic rnameal paint of approved make and brand in/c smoothening surface by sand papering etc. in/c using of approved putty etc. on the surface.(page-343,it-8aiv)other than high gloss	17.78	m2	53.73	955.32
31	G.I. rain water spout 75mm dia and 600 to 750mm long supplied fitted and fixed complete with two coats of paint to both exposed portion	4	No	136.35	545.4
				Total	296788.37

Signature of Tenderer: -



Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity
Illambazar Birbhum

SCHEDULE FOR REPAIRING OF KANDAR BRIDGE ON SANTOSHPUR TO DHOOLPUR ROAD WITHIN JOYDEV-KENDULI GP UNDER 3 rd F.C.2010-2011 FUND.

Ref: - NIT No. – 17/IPS/2010-11


Date- 21.01.2011

Sl. No.-09

SL NO	DESCRIPTION OF ITEMS	TOTAL QNTY	UNIT	RATE in/c 1 % cess	UNIT	AMOUNT (Rs)
1	Earthwork in excavation of the trenches in all sorts of soil in/c mixed soil but ex/c stoney moorum soil in/c removing, spreading or stacking etc all complete.	39.7	m3	73.29	/m3	2909.32
2	Sand filling in foundation trenches with good quality sand free from earth in layers not exceeding to 15cm in/c spredding each layers by layers use water and packing and ramming layer by layer complete in/c all cost and carriage of materials.sand should be approved by E.I.C.	11.09	m3	344.85	/m3	3823.35
3	single layer BFS in foundation with picked jhama bricks in/c ramming and dressing bed to proper level and filling up all joints with local sand in/c cost and carriage of all materials as per direction.	61.17	m2	194.65	/m2	11906.74
4	Providing and laying cement concrete M-15 grade without reinforcement in any wing wall with approved stone chips in/c cleaning of agreeegate and sand as necessary curing with water with cost and carriage of all materials complete but excluding the cost of reinforcement and shuttering	10.98	m3	4109.92	/m3	45108.43
5	Providing and laying cement concrete M-20 grade without reinforcement in any wing wall with approved stone chips in/c cleaning of agreeegate and sand as necessary curing with water with cost and carriage of all materials complete but excluding the cost of reinforcement and shuttering	3.1	m3	4818.63	/m3	14925.71
6	Hire and labour charges for shuttering with centering and necessary staging up to 4m using approved stout prop and thick hard wood planks of approved thickness with required bracing for concrete slab beam column lintel curved or straight in/c fitting,fixing and striking out after completion of works.(25mm to 30mm th.wooden shuttering). (b) without staging in foundation.	10.95	m2	162.42	/m2	1778.82
7	1st.class brick work in cement mortar in 1:6 proportion.	32.72	m3	3283.12	/m3	107407.27
8	Plaster with sand and cement mortar in/c rounding off corners of chamfering corners as directed and including raking out joints or roughening of concrete surface,curing with cost and carriage of all materials (a) 15mm with 6:1 cement mortar	98.76	sqm	97.56	/sqm	9635.03
9	Neat cement punning on cement plaster surface.	98.76	sqm	28.33	/sqm	2797.87

10	Earth work in filling in in foundation trenches or plinth with good earth in layer not exceeding 150mm in/c watering and ramming etc.layer by layer complete. (payment will be made on finished quantity of work).land arranged by the contractor.	43.2	cum	240.89	/cum	10406.45
11	providing weep holes (150x 75)mm in abutment or wing wall for the entire thickness, with slope 1:20 towards drainage surface, including packing with different sizes of brick bats or boulders of approved quality and size as per direction of E.I.C.	20	nos	106	/no	2120.00
12	Labour for spreading moorum in layers, including compacting manually by hand roller as per direction of E.I.C. including necessary watering supply of moorum at working site completed in all respect.	48	cum	509.6	/sqm	24460.80
13	labour for chipping of concrete surface before taking up plastering work.	48.65	sqm	12.43	/sqm	604.72
						237884.50
					say,	237885.00

Signature of Tenderer: -



**Executive Officer
Illambazar Panchayet Samity**

Illambazar Panchayet Samity
Illambazar Birbhum
Schedule of work

Name of the work: - CONSTRUCTION OF GUARD WALL OF KHADIM GORE,
Mouza: -Dhansha, J.L. No: -19, Plot No: -661, P.S: -Panrui, Dist: -Birbhum.
[From BEUP fund]

Ref: - NIT No. – 17/IPS/2010-11


Date- 21.01.2011

Sl. No.-10

Sl No	Description of Item with Quantity	Rate @ Rs.	Amount Rs.
1	Earthwork in excavation in foundation of structure ---- With pumping out water in/c shoring [Page 203 it 1(a)] Quantity:-25.65 Cum.	49.70 /Cum.	1274.80
2	Sand filling in foundation trenches ----- [Page 207, it. 9] Quantity: - 1.468 Cum.	326.60 / Cum.	479.40
3	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed --- Or local earth/sand. [Page 319 SI-07/b] Quantity: - 19.575 Sqm	153.80 /Sqm	3010.60
4	Providing and laying Cement concrete with or without reinforcement in any part ----- complete. 1: 2: 4 concrete. [Page 220, it. 30(b)] Quantity: -5.626 Cum	4307.28 /cum	24,232.80
5	1st class brick work (1:6) in sand cement mortar----- [Page 217, it. 23c.] Quantity: -33.694 Cum	3267.00 /cum	1,10,078.30
6	Supplying bending & binding in laying in position steel reinforcement of different dimension ----- For M.S rounds/Tor Steel/HYSD bars. [Page 215, it. 19] Quantity:- 0.351 MT	59173.00 /MT	20,769.70
7	Providing form work and staging in/c hire & labour charges for the same as required for foundation concrete ----- [Page 208, it. 11] Quantity: -19.71 Sqm	84.00 /Sqm.	1655.60
8	Plastering with sand cement mortar in/ c rounding- off corner ----- all materials. With 4:1 cement mortar. 15 mm th plaster [Page 218, it. 26/a/ii] Quantity: - 107.36 Sqm	73.90 / Sqm.	7933.90
9	Net cement punning. [Page219, it.27] Quantity: - 107.36 Sqm	33.50 /Sqm.	3596.60
10	Providing weep holes (150 x 75) in abutment or wing wall for the entire thickness, with slope 1:20 towards drainage surface. [Page296, it.16] Quantity: - 8 Nos.	106.00 / Each	848.00

[The nomenclature & rate collected from PW(Road) Sch.
As per mentioned page and item]

Rs. 1, 73,879.70
Add for Cess @ 1%: -Rs. 1,739.00
Total: -Rs.1, 75,618.70
Say 175000.00



Signature of Tenderer: -

Executive Officer
Illambazar Panchayet Samity

Illambazar Panchayet Samity
Illambazar Birbhumi

Schedule of work

Name of the work: - CONSTRUCTION OF GUARD WALL OF PIYAL GORE,
Mouza: -Dhansha, Plot No: -920, P.S: -Panrui, Dist: -Birbhumi. [From BEUP fund]

Ref: - NIT No. – 17/IPS/2010-11

Date- 21.01.2011

SL No.-11

SI No	Description of Item with Quantity	Rate @ Rs.	Amount Rs.
1	Earthwork in excavation in foundation of structure ---- With pumping out water in/c shoring [Page 203 it 1(a)] Quantity:- 23.76 Cum.	49.70 /Cum.	1180.90
2	Sand filling in foundation trenches ----- [Page 207, it. 9] Quantity: - 1.35 Cum.	326.60 / Cum.	440.90
3	Single layer brick flat soling of picked jhama bricks in/c ramming and dressing bed --- Or local earth/sand. [Page 319 SI-07/b] Quantity: - 18.00 Sqm	153.80 /Sqm	2768.40
4	Providing and laying Cement concrete with or without reinforcement in any part ----- complete. 1: 2: 4 concrete. [Page 220, it. 30(b)] Quantity: -5.516 Cum	4307.28 /cum	23,759.00
5	1st class brick work (1:6) in sand cement mortar----- [Page 217, it. 23c.] Quantity: -41.063 Cum	3267.00 /cum	1,34,152.80
6	Supplying bending & binding in laying in position steel reinforcement of different dimension ----- For M.S rounds/Tor Steel/HYSD bars. [Page 215, it. 19] Quantity:- 0.33 MT	59173.00 /MT	19,527.10
7	Providing form work and staging in/c hire & labour charges for the same as required for foundation concrete ----- [Page 208, it. 11] Quantity: -18.79 Sqm	84.00 /Sqm.	1578.40
8	Plastering with sand cement mortar in/ c rounding- off corner ----- all materials. With 4:1 cement mortar. 15 mm th plaster [Page 218, it. 26/a/ii] Quantity: - 114.84 Sqm	73.90 / Sqm.	8486.70
9	Net cement punning. [Page219, it.27] Quantity: - 114.84 Sqm	33.50 /Sqm.	3847.10
10	Providing weep holes (150 x 75) in abutment or wing wall for the entire thickness, with slope 1:20 towards drainage surface. [Page296, it.16] Quantity: - 22 Nos.	106.00 / Each	2332.00

[The nomenclature & rate collected from PW(Road) Sch.
As per mentioned page and item]

Rs. 1,98,073.30
Add for Cess @ 1%: -Rs. 1,980.70
Total: -Rs.2, 00,054.00
Say: -Rs.2, 00,000.00

Signature of Tenderer: -


Executive Officer
Illambazar Panchayet Samity